**Bruhath Bangalore Mahanagara Palike**

**Tender Notification No: BBMP/EE/Proj/RRN/TEN/02/2021-22 Date:31.05.2021**

**Indet No:-BBMP/2020-21/OW/WORK_INDENT47605**

**SCHEDULE -B**

**Name of Work:- Removal of Debries Near STP Plant In J.P.Park Ward No.17**

| Sl No | Item Name | Unit | Quantity | Rates in | |
|---|---|---|---|---|---|
| | | | | Figures | words |
| 1 | Earth work for lowering and levelling the ground other than foundation works by mechanical means upto 3.00 depth, including providing shoring and strutting, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavation earth to the extent required including the cost of labour & HOM of machineries, as per drawing and technical specification. | Cum | 11875.46 | 66.80 | Rupees Sixty Six and Eighty Paise Only |
| 2 | Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually ( other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables ) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and | Cum | 87.00 | 276.03 | Rupees Two Hundred Seventy Six and Three Paise Only |
| 3 | Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. | Cum | 11875.46 | 116.52 | Rupees One Hundred Sixteen and Fifty Two Paise Only |

Signature of Contrcator.

Executive Engineer (Project)
Rajarajeshwari nagar Zone
BBMP

Executive Engineer (Project)
Bruhat Bangalore Mahanagar Palike
Rajarajeshwari Nagar Zone

Signature of Contrcator.



Scanned by TapScanner